




Always check the website for the most updated specifications: www.americh.com











All bathtub dimensions are ± 1/2'

**Builder Series** 







**Luxury Series** 

# **Platinum Series**


# Combination


(pump and blower location only)














## **INSTALLATION TIPS**

- Install according to Owner's Manual and local codes. Always consult your local plumber for recommendations.
- Certain options or altering the pump/blower location may cause the pump/blower to extend beyond the tub decking.
- Airbath III units may be 1  $\frac{1}{2}$ " 2  $\frac{1}{2}$ " taller than stated.
- Hot water supply should be 65-75% of the tub capacity or greater.
- Cut Dimensions: 64"x34" It is recommended to wait for unit to arrive before cutting
- All specifications are subject to change without notice.
- The combination of multiple systems and options may require components to stick out and/or be remotely installed in the field.

#### **DIMENSIONS**

66" x 36" x 22" (1676 x 914 x 559 mm) Whirlpool Operating Gallons = 50 (Liters = 189) Gallon to Overflow = 75 (Liters = 284)

**MATERIAL:** Acrylic TUB FLOOR: Non-Textured

**UNDERMOUNT:** Yes

- Advise Americh when ordering to ensure there are no issues with deck mounted controls.
- Always take dimensions directly from the unit.

#### **ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

### **STANDARD EQUIPMENT:**

Adjustable Feet

#### **OPTIONAL ACCESSORIES**

- Chromatherapy\*
- Grab Bars: 9" \* 14" 16"
- High Density Insulation\*
- iBath Sound System
- Inline Heater (whirlpool only)
- Jets: Additional or Rotary\*
- Lo Profile Tub Edge
- Ozone System (whirlpool and/or Airbath only)
- Pillows: 12" \* Angle
- Remote Control Upgrade (select series only)
- Serenity Soak (tub only)
- Syllent Pump with Heated Air\*
- Thermal Comfort System (TCS cannot be used with VSM)
- Tile Flange Kit
- Trim Kit Upgrade\*
- Vibro Sonic Massage (VSM cannot be used with TCS)
- Waste & Overflows Upgrades
  - Cable Drive Waste & Overflow\*
  - PVC Waste & Overflow+
  - Linear Waste & Overflow

## (\*) Standard on Platinum Series

(+) Standard on Luxury Series

### **CODES AND COMPLIANCE**

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8

Contact Americh for additional approvals.