
# **MERICH**

ANDRINA™ 7236


Always check the website for the most updated specifications: www.americh.com





## Airbath System II

Blower must be remotely located (Diagram is required for custom blower connection locations)



LEGEND:

BLOWER OUTLET

REMOTE CONTROL (INVISIBLE MAGNETIC HOLDER)

### **STANDARD EQUIPMENT:**

- Americh Remote Control
- Integral Waste & Overflow with Polished Chrome trim Available with polished brass, polished nickel, satin nickel, oil rubbed bronze or white trim at no additional charge if specified at the time of order. Requests after order is shipped are subject to a \$75 list charge for trim

### **INSTALLATION TIPS**

- Install according to Owner's Manual and local codes.
- Hot water supply should be 65-75% of tub capacity or greater.
- Always consult your local plumber for recommendations as installations will vary.



**DIMENSIONS:** 72" x 36" x 24" deep (1829 x 916 x 533 mm)

Gallon to Overflow = 85 (Liters = 322) Height to Overflow = 1534'' (400 mm)

MATERIAL: Polymer Composite (All Americh Standard Colors)

TUB FLOOR: Non-Textured

**UNDERMOUNT: No** 

#### **ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

### **OPTIONAL ACCESSORIES**

- Pillows: 12" Angle
- Stainless steel chain and stopper kit
- Waste & Overflow Upgrades
  - Linear Waste & Overflow

#### CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)

• ANSI Z124.1 • ANSI A112-19.7 • ANSI A112.19.8 Contact Americh for additional approvals.