




Always check the website for the most updated specifications: www.americh.com










All bathtub dimensions are $\pm 1/2$ ".

Airbath System II



Factory installed blower may only be placed in this location.

LEGEND:



BLOWER



ON/OFF CONTROL

ACCESS PANEL (PROVIDED BY FACTORY)

STANDARD EQUIPMENT:

 Integral Waste & Overflow with Polished Chrome trim Available with polished brass, polished nickel, satin nickel, oil rubbed bronze or white trim at no additional charge if specified at the time of order. Requests after order is shipped are subject to a \$75 list charge for trim

· Lift bag is provided

INSTALLATION TIPS

- Install according to Owner's Manual and local codes.
- Access panel for Airbath® systems included with the Contura series.
- \bullet Hot water supply should be 65-75% of tub capacity or greater.
- Always consult your local plumber for recommendations as installations will vary.

DIMENSIONS:

72" x 32" x 24" (1829 x 813 x 610 mm) Gallon to Overflow = 95 (Liters = 360) Factory installed integral drain.

MATERIAL: Acrylic (White and Biscuit Only)

TUB FLOOR: Non-Textured

UNDERMOUNT: No

ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

OPTIONAL ACCESSORIES

- Chromatherapy
- Pillow: 12"
- Remote Control Upgrade
- Waste & Overflow Upgrades
 - Linear Waste & Overflow

CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7 ANSI A112.19.8 Contact Americh for additional approvals.

